

Bid Tabulation
2024 ARPA West Stewart Utility District Water Meter Installation
Bid Opening: Wednesday, June 18th, 2025 at 2:00 PM local time
Rye Engineering, PLC located at 4210 West Main Street, Erin, TN 37061

Contractor Name	Greenway Enterprise LLC
State Contractor License Information on Outside of Envelope	YES
5% Bid Bond or Cashiers Check	YES
Iran Divestment Act	YES
Non-Boycott of Israel	YES
Drug-Free Workplace Affidavit	YES
Contractor's Attestation Regarding Illegal Immigrants	YES
Certification Regarding Debarment & Suspension	YES
Certification Regarding Use of Women/Minority Subcontractors	YES
Byrd Anti-Lobbying Amendment Certification	YES

Unit Price Bids

Item No.	Description	Quantity	Unit	Unit Price	Total Price
1	Install 3/4" AMI Meter Assembly; includes meter, AMI endpoint, yoke, box, leveling blocks, gravel, and connection to existing service line. Meter and AMI endpoint to be supplied by Owner. All other materials and labor to be provided by Contractor.	236	EA	\$955.00	\$225,380.00
2	Install 2" AMI Meter Assembly; includes meter, AMI endpoint, yoke, box, leveling blocks, gravel, and connection to existing service line. Meter and AMI endpoint to be supplied by Owner. All other materials and labor to be provided by Contractor.	2	EA	\$2,800.00	\$5,600.00
3	¾" HDPE SDR-9 Class 200 CTS	3000	LF	\$3.75	\$11,250.00
4	Service Roadway Bore/Punch (to include 2" PVC Sleeve)	750	LF	\$4.50	\$3,375.00
5	Service Saddle Tap, Corporation Stop, Curb Stop Lock Wing	17	EA	\$800.00	\$13,600.00
6	Concrete Replacement (as required)	18	CY	\$500.00	\$9,000.00
7	Asphalt Repair (as required)	50	TONS	\$150.00	\$7,500.00
8	Crushed Limestone Gravel for Trenching Backfill, Bedding, Base, and Driveways, etc.	325	TONS	\$27.00	\$8,775.00
9	All Erosion Prevention and Sediment Control and Seeding and Strawing	1	LS	\$5,000.00	\$5,000.00
Total of All Unit Price Items:				\$289,480.00	

Date: 06/18/2025



X

Seth W. Rye

I hereby Certify that this Bid Tabulation is accurate for all bids received for this project on the date and time specified above.