

**ADDENDUM NO. 3**

**2024 CDBG NEW JOHNSONVILLE COLLECTION SYSTEM REHABILITATION**

**CITY OF NEW JOHNSONVILLE**

**PROJECT #: NJ-2025-3**

**CURRENT PROPOSAL OPENING DATE/TIME– WEDNESDAY, JUNE 24<sup>th</sup> , 2026 AT 2:00 PM LOCAL TIME**

**TO:** ALL PROSPECTIVE PROPOSERS

**FROM:** Rye Engineering, PLC

**DATE:** June 18, 2026

This Addendum is for answering questions brought up during the bidding process and addressing a clarification on the existing sewer services. This is the final addendum prior to the bid opening. No more questions will be answered.

***Clarification of construction plans:***

An investigation was performed this week by City of New Johnsonville employees, and a determination has been made that there are three (3) sewer services that will need to be tied into the proposed line, due to the existing service discharging into the line that is to be abandoned. The existing line to be abandoned shall also have a permanent boot placed in the abandoned line. These items have been revised in the plans, and in the bid form.

***Questions by Contractors:***

- 1. Can the 6" waterline on Sunset Drive be shut down temporarily, and bypassed with a 2" HDPE or PEX line laying on top of the ground?**


**ANSWER:** *No, the existing water line cannot be bypassed with a 2" line due to fire flow. If necessary, New Johnsonville will entertain a 6-inch bypass where fire flow can be met, but preferably no bypass if possible.*

- 2. How accurate is the location of the existing sewer line under / next to the existing residence on Map 094H Group A Parcel 011.00?**

**ANSWER:** *The Location of the manholes were surveyed with survey-grade accuracy. However, the line was drawn in by drawing a straight line from EX-MH1 to the existing manhole to the North of Sunset Drive. It should be very close, however; we have no way to account for any pipe offsets etc. if it occurs in that section 20 feet deep.*

- 3. If the existing sewer line / manhole is leaking into our trench, and we have to dewater, can we dewater into the sanitary sewer?**

**ANSWER:** *Yes, this is fine to dewater into the sanitary sewer.*



**4. How Wide does the bypass road need to be? Is 24-hour traffic control required?**

**ANSWER:** *The bypass road or temporary road needs to be at a minimum of 15 feet wide to fit the Fire Truck through if needed. 24-hour traffic control is not required, but lighting, barricades, and signage must be placed to prevent anyone from driving into the project area.*

Please complete acknowledgement of receipt of this addendum and email the response to [mwesterman@ryeengineering.com](mailto:mwesterman@ryeengineering.com). Likewise, please put acknowledgement of this addendum on the bid form.

**\*\* End of Addendum No. 3 \*\***

Acknowledgment of receipt:

\_\_\_\_\_ (Company Name)  
\_\_\_\_\_ (Signature) \_\_\_\_\_ (Date)